

Notice to Bidders

Town of Jackson, Washington County

The Town of Jackson, Washington County is accepting bids for asphalt paving for the following roads:

1. Sherman Road, East Town Line to CTH M.

Work to be provided will consist of pulverizing and placement of a 2.25" binder course and a 1.75" surface course.

2. Spring Valley Road, CTH M to Church Road.

Work to be provided will consist of placement of a tack coat and 1.5" surface course of asphalt on a binder placed in 2022.

Bids will be accepted until 12:00 p.m. on June 13, 2024 at the Town of Jackson Town Hall, 3146 Division Road, Jackson, WI 53037. Bids will be opened and publicly read at the Town Board meeting which will be held on June 13, 2024 at 7:00 PM. at the Town Hall. The Town Board will discuss the bids and may award the project during the meeting.

For further information please contact Ron Eickstedt, Highway Supervisor by calling 262-305-5355 or Bob Eichner Town Clerk at 262-677-4048.

Bid documents may be obtained from the town website (townofjacksonwi.gov), the Town highway department, or the office of the Town clerk. The clerk's office is generally open Monday through Thursday 9:00 AM to 4:30 PM and Friday 9:00 AM to 1:00 PM. If you are making a special trip to the office, please call (phone 262-677-4048) to ensure there will be someone available to assist you.

All roads listed are proposed for completion in 2024, however, the Town of Jackson reserves the right to accept or reject any, or all bids or any parts thereof, waive any informalities in the bidding process and to accept the bid proposal or portion of a proposal deemed most advantageous to the Town.

TOWN OF JACKSON – WASHINGTON COUNTY
2024 PROJECT DESCRIPTIONS – ASPHALT PAVING

Bidder Information:

Name: _____

Company: _____

Address: _____

Phone: _____ Contact Name: _____

Email: _____

ASPHALT RECONSTRUCTION

<u>DESCRIPTION</u>	<u>QUANTITY</u>	<u>UNIT PRICE</u>	<u>TOTAL PRICE</u>
<u>SHERMAN ROAD, EAST TOWN LINE TO CTHM</u>			
Pulverize existing pavement, grading, and placement of a 2.25", grade 3 asphalt binder course Estimated tonnage is 1645 tons (23' x 5130')			
	_____ Tons @	\$ _____	\$ _____
Placement of a 1.75", Grade 2 Asphalt surface course, 1.5" thick Estimated tonnage is 1235 tons (23' x 5130')			
	_____ Tons @	\$ _____	\$ _____
Project Sub-Total	_____ Dollars		\$ _____
<u>SPRING VALLEY ROAD CTH M TO CHURCH RD</u>			
Placement of an 1.5" Grade 2 Asphalt surface course. (binder placed in 2022) Estimated tonnage is 1065 tons (23' x 5333')			
	_____ Tons @	\$ _____	\$ _____
Project Sub-Total	_____ Dollars		\$ _____
2024 Project Total	_____ Dollars		\$ _____

Conditions

1. A portion of the Sherman Road reconstruction will be funded by a Wisconsin DOT Local Road Improvement Program grant.
2. Unit costs for the above paving items shall include milling and matching all abutting road intersections and asphalt driveways to 3 feet from the edge of the new roadway pavement.
3. Some adjustment to the centerline profile of Sherman Road may be necessary. All additional gravel base course material necessary for this purpose will be provided by the Town of Jackson.
4. This work does not include placement of gravel shoulders nor pavement marking.
5. Contractor shall provide all necessary construction traffic control signage and equipment in accordance, with the Manual on Uniform Traffic Control Devices to complete this contract.

BIDS WILL BE AWARDED ON TOTAL PRICE, NOT UNIT PRICE.

TONNAGE AND LENGTHS PROVIDED ARE ESTIMATES AND MUST BE VERIFIED BY BIDDER.